

Krannert Center for the
Performing Arts

Solar Project Feasibility Study

**University of Illinois
at Urbana-Champaign**

Project Number: U12239

Summary of Findings

March 25, 2014

Phase 1

*March 1, 2013
(revised August 29, 2013)*

Phase 2

95% Submittal

March 25, 2014

SUMMARY OF FINDINGS

This Feasibility study considers the potential placement of a Photovoltaic array on the roof of Krannert Center for the Performing Arts (KCPA). The Study was conducted in two phases, the reports of which are included herein. A construction budget of five hundred eighty-five thousand dollars (\$585,000), excluding contingencies, was proposed by the Student Sustainability Committee.

Based on shadow studies, it was determined that placement of a photovoltaic array on the roof of the Great Hall would maximize the potential power gain, as compared to other locations at KCPA. However, structural analyses have shown that the roof structure would require strengthening prior to the application of any new load. Additionally, based on its age, it is recommended that the roofing be replaced prior to the installation of a photovoltaic array. Access to the roof is cumbersome, and is also in need of improvement. The opinion of probable construction cost for this associated work exceeds the five hundred eighty-five thousand dollar (\$585,000) construction budget. Without considering these associated projects in the payback analysis, the complexities of constructing a PV array on the roof structure diminish the economical effectiveness of a roof mounted PV array as compared to a ground-mounted system, assuming the ready availability of real estate.

Based on these findings, it is the recommendation of Hanson Professional Services Inc. (Hanson) that a photovoltaic array not be placed on the roof of the Great Hall at KCPA, and that consideration be given instead to directing the available funds to a location that is more readily suited to its construction.

The following matrix captions the primary Objectives of the study, and directs the reader to the Section(s), Article(s) and / or Appendix(ces) in the Study that addresses the objective. A recapitulation of the Opinions of Probable Construction cost is also presented.

OBJECTIVE		REFERENCE ARTICLE OR SECTION		COMMENTARY
		PHASE 1	PHASE 2	
1.	Conduct project kick-off meeting with University personnel (KCPA and Facilities & Services).	Kick-off meeting was held January 18, 2013 at UIUC.		
2.	Review record documents of existing construction for the study areas and existing information on PV project feasibility.	Existing Plans, circa 1966 and 1967. Architect: Harrison & Abramovitz. Structural Engineers: Lev Zetlin & Associates. Mechanical/Electrical Engineers: Cosentini Associates		

OBJECTIVE		REFERENCE ARTICLE OR SECTION		COMMENTARY
		PHASE 1	PHASE 2	
3.	Perform site survey of the study areas and identify probable installation locations of exterior solar PV arrays and interior PV inverters. Locations will be assessed for future system maintenance and connection to the commercial power grid.	Site Visits performed on February 15, 2013. PV information identified in Section 5. Design Concepts , pp. 8-9. Appendix D – Shadow Studies		Shadow studies directed PV placement array on roof of Great Hall. 10 degree angle of inclination of PV array selected for aesthetic considerations.
4.	Identify probable PV system size and number, type and size of PV arrays based on preliminary project construction budget for input on the rendering.	Section 5. Design Concepts , pp. 8-9 Appendix C – Schematic Roof Plan – Great Hall		
5.	Produce a preliminary report including a summary of initial findings and three exterior renderings of the facility depicting the visual impact the installation would be expected to have on the KCPA. The renderings will be produced in Revit by modeling the PV system design then overlaying that geometry onto three KCPA building photographs taken from the South, East, and West points of view.	Draft Report produced March 1, 2013. Renderings – Appendix E – Renderings – Line Type for Great Hall at 34° and 10° Inclination of Solar Panels and Overall ground Level Photo Renderings		
6.	Respond to the University's review comments and meet with University personnel to disposition those comments.	Responded to UIUC's comments on March 29, 2013. Phase 1 Report - Appendix I – UIUC Review Comments		

OBJECTIVE		REFERENCE ARTICLE OR SECTION		COMMENTARY
		PHASE 1	PHASE 2	
7.	Update report and submit final preliminary report copy.	Revised Report and submitted to UIUC August 29, 2013.	Phase 2 report – Submitted March 25, 2014.	
8.	Evaluate existing electrical system to determine appropriate location to interconnect PV system. Determine maximum available solar power that can be effectively connected to the existing electrical system based on the available mounting area for the solar modules.	Section 5. Design Concepts – pp. 8 – 9.		Micro-inverters are proposed to be located at the PV array on the roof. New power distribution panel would be located on the Booth level. Maximum anticipated power generation = 80KW.
9.	Evaluate the capacity of the existing roof structure to support the gravity and wind loads induced into the structure by the PV arrays.	Initial Findings – Article 1.5 Special Conditions , p. 6.	Section 1. Structural Evaluation , pp. 4-7.	Strengthening of existing structure is required prior to placement of PV array. OPCC is \$300,000.
10.	Evaluate the general condition of the existing roofing materials for the study areas to determine the anticipated remaining useful life of the roof(s).	Initial Findings – Article 1.5 Special Conditions , pp. 5 and 6.	Section 2. Roofing Replacement , p. 7.	Roofing replacement is recommended. OPCC is \$360,000.

OBJECTIVE		REFERENCE ARTICLE OR SECTION		COMMENTARY
		PHASE 1	PHASE 2	
11.	Develop schematic drawings and narrative description of proposed improvements.	Section 5. Design Concepts – pages 8 – 9. Appendix C – Schematic Roof Plan – Great Hall Appendix D – Shadow Studies		
12.	Coordinate identification of vibration and noise issues that may be expected to be imposed by the PV system with subconsultant along with recommended design criteria to mitigate these issues.	Article 1.5 Special Conditions , page 6.	Section 4. Noise and Vibration Analysis , page 7 Appendix B – Kirkegaard Report – Noise and Vibration Analysis	Report presents general recommendation for decoupling PV array from building structure. Further study is recommended if project advances to design.
13.	Prepare an Opinion of Probable Construction Cost for proposed improvements.	Section 6. Opinion of Probable Construction Cost , pages 9 - 10. Appendix B – Payback Analyses and Opinion of Probable Construction Cost for Roof Top Construction Activities	Section 6. Opinion of Probable Construction Cost , page 8. Appendix C – Opinion of Probable Construction Cost – General Work	Construction budget is \$585,000 excluding contingencies. Depending upon extent of associated work assigned to this project, total OPCC is \$1.3M excluding contingency and PSC fees.
14.	Prepare an energy saving payback analysis of proposed improvements using University provided utility costs.	Section 7. Payback Analysis , page 10. Appendix B – Payback Analyses and Opinion of Probable Construction Cost for Roof Top Construction Activities	Section 7. Payback Analysis , page 8.	Payback period cannot be accurately determined due to the extent of associated projects that are necessary prior to the installation of the PV array.

OBJECTIVE		REFERENCE ARTICLE OR SECTION		COMMENTARY
		PHASE 1	PHASE 2	
15.	Update renderings produced in Phase 1.	Appendix E - Renderings – Line Type for Great Hall at 34° and 10° Inclination of Solar Panels and Overall ground Level Photo Renderings	No change since Phase 1.	
16.	Evaluate the potential benefits of electrochromic glazing in the west curtain wall of the Great Hall.	Appendix H – Electrochromic Glazing Evaluation for Great Hall		

Recapitulation of Opinion of Probable Construction Cost

ITEM	Phase 1 OPCC	Phase 2 OPCC
Roofing Replacement	Not included	\$360,000
Construction Access and General Construction	\$128,000	\$132,000
Roof Scuttle Improvements	Not included	\$15,000
Roof Truss Strengthening	Not included	\$300,000
Noise and Vibration Mitigation	Not included	\$36,000
Electrical conduit / routing	\$117,000	\$117,000
PV cells and Micro-inverters	\$326,000	\$326,000
Electrical Power Distribution Equipment	\$10,000	\$10,000
Kiosk	\$4,000	\$4,000
TOTAL (excluding contingencies)	\$585,000	\$1,300,000

Krannert Center for the
Performing Arts

Solar Project Feasibility Study

**University of Illinois
at Urbana-Champaign**

Project Number: U12239

Phase 1

March 1, 2013

(revised August 29, 2013)

Table of Contents

EXECUTIVE SUMMARY	3
1. DESCRIPTION, OPTIONS, OBJECTIVES, PROGRAM AND SPECIAL CONDITIONS.....	4
1.1 <i>Project Description.....</i>	4
1.2 <i>Master Plan Impact and Options</i>	4
1.3 <i>Major Project Objectives, and Design Requirements</i>	4
1.4 <i>Program Summary.....</i>	5
1.5 <i>Special Conditions</i>	5
2. CODES AND PERMITS.....	7
2.1 <i>Applicable Codes and Standards</i>	7
2.2 <i>Applicable Permits</i>	7
3. SITE REQUIREMENTS	7
4. MAINTENANCE BUDGET & ENERGY BUDGET FOR SUSTAINABILITY.....	8
5. DESIGN CONCEPTS	8
6. OPINION OF PROBABLE CONSTRUCTION COST.....	9
7 PAYBACK ANALYSIS	10
8. PROJECT SCHEDULE	10
9. UIUC REVIEW COMMENTS	10

Appendices

Appendix A – Site Plan

Appendix B – Payback Analyses and Opinion of Probable Construction Cost for Roof Top Construction Activities

Appendix C – Schematic Roof Plan – Great Hall

Appendix D – Shadow Studies

Appendix E – Renderings – Line Type for Great Hall at 34° and 10° inclination of Solar Panels and Overall Ground Level Photo Renderings

Appendix F – Conceptual Crane Placement

Appendix G – Generic Wiring Diagram, Example of Micro-inverter and Product Data Sheet for Typical Photovoltaic Panel

Appendix H – Electrochromic Glazing Evaluation for Great Hall

Appendix I – UIUC Review Comments

Copyright © 2012 by Hanson Professional Services Inc. All rights reserved. This document is intended solely for the individual or the entity to which it is addressed. The information contained in this document shall not be duplicated, stored electronically, or distributed, in whole or in part, by anyone other than the recipient without the express written permission of Hanson Professional Services Inc., 1525 S. Sixth St., Springfield, IL 62703, (217) 788-2450, www.hanson-inc.com. Unauthorized reproduction or transmission of any part of this document is a violation of federal law. Any concepts, designs and project approaches contained herein are considered proprietary. Any use of these concepts and approaches by others is considered a violation of copyright law.

Executive Summary

The purpose of the study is to examine the feasibility of installing a solar photovoltaic (PV) system on one or more of the roofs at Krannert Center for the Performing Arts (KCPA). The study also addresses the potential use of electrochromic glazing on the west curtain wall of the Great Hall.

Phase 1 of the study, presented herein, examines the visual impact on the facility and presents to the University an opinion of probable construction cost (OPCC), general considerations of construction phasing and associated general construction, and a simple payback analysis for the PV array. As part of Phase 1, the space requirements for the PV system's inverters have been identified along with potential installation location(s) within the KCPA facility.

If after considering the findings of Phase 1 of this study the University elects to further evaluate the feasibility of installing a PV array atop one or more of the roofs of the KCPA facilities, this study will continue with a second phase (Phase 2). This second phase will include an evaluation of the structural load the PV system would impose on the facility (gravity and wind), and an assessment of the general condition of the existing roofing material to identify the anticipated remaining useful life of the roofs. A noise and vibration analysis will also be included in Phase 2 to identify the acoustic impact the PV system installation may be expected to have on the performance spaces within the facility.

A five hundred eighty-five thousand dollar (\$585,000) construction budget, excluding contingencies, has been established for this project. Based on the assessments that have been completed during Phase 1, approximately four hundred fifty-seven thousand dollars (\$457,000) would be directed toward the purchase and installation of solar panels and electrical work, with the remaining, one hundred twenty-eight thousand dollars (\$128,000), being directed toward the costs of the associated general construction and construction access. This results in a net effective installed cost of between seven dollars and twenty-five cents and seven dollars and fifty cents (\$7.25 and \$7.50) per Watt. For general consideration, using an offset in consumption of 105,120 Watts / year, and a utility cost of twelve cents (\$0.12) / Watt, the estimated payback period is substantially longer than 25 years.

The cost of electrochromic glazing at the west curtain wall of the Great Hall is not included in the overall project cost assessment described in the preceding paragraph. It is generally approximated, thought to be on the order of three hundred thousand dollars (\$300,000) to three hundred fifty thousand dollars (\$350,000). Energy savings resulting from the use of electrochromic glazing are estimated to be under one thousand five hundred dollars (\$1,500) annually.

1. Description, Options, Objectives, Program and Special Conditions

1.1 Project Description

This project would construct PV cells atop one or more of the roofs at Krannert Center for the Performing Arts (KCPA) and or install electrochromic glazing on the west curtain wall of KCPA. Refer to Appendix A for an overall Site Plan.

1.2 Master Plan Impact and Options

This project does not add to or subtract from the campus inventory of facilities or spaces, nor does it have any appreciable impact on current space use. Its goals and objectives are described below. In consideration of those goals, it may be appropriate to consider installing PV cells at another facility on or adjacent to campus should it be concluded that the installation of PV cells at KCPA is not feasible or desirable. For general comparison purposes, payback analyses for the roof-mounted PV array at Krannert and a ground-mounted array (assumed to be locatable on a generally open, level site) are included in Appendix B.

1.3 Major Project Objectives, and Design Requirements

This project has been proposed to Facilities and Services by the Student Sustainability Committee (SSC). The understood objectives of the project would be to partially offset the power demand of the KCPA facility with sustainable (solar) power and to provide an example of how such energy sources can be used in facilities such as KCPA. These PV sources would be PV cells positioned atop one or more of the roofs of KCPA. Several decision criteria are to be evaluated in this assessment. The primary considerations are:

- A. The cost / benefit ratio of the PV installation. Payback analyses are included in the first phase of the study.
- B. The visual impact to the facility needs to be considered. This is included in this first phase of the study.
- C. The acoustic impact to the facility needs to be considered. This will be deferred to Phase 2 of the study.
- D. The installation will need to be executed in a manner that minimizes disruption to the regularly scheduled performances, recordings and other uses of KCPA. Accordingly, the premium cost of labor during non-standard working hours needs to be included in the assessment of costs.
- E. The maintainability of the PV system and the roof(s) on which the PV array is / are placed needs to be considered. The impact the addition of PV cells will have on the integrity and maintainability of the roof system.

1.4 Program Summary

The intended program seeks to derive the benefit of solar energy to offset the building's power consumption within an overall construction budget of \$585,000, excluding bid and construction contingencies. This budget is to be directed toward the PV installation, and does not include the cost of replacement of any other building features, such as roofing, that should otherwise be included as part of the building's regular maintenance.

1.5 Special Conditions

Architectural

Layout of the PV cells should maximize exposure to the sun, limit visual impact on the facility and, within the foregoing constraints, facilitate maintenance of the building and the new equipment as much as reasonably practicable. Also, the layout must not obstruct roof access with respect to existing openings. Given these objectives, the roofs of the Great Hall, Drama Theater and Music Theater were initially considered as probable locations for PV arrays. However, the focus of the study was ultimately directed to the roof of the Great Hall. This decision was reached in consideration of maximizing sun exposure (the backstage housing projections at the Drama Theater and Music Theater block the afternoon sun to a much greater extent than the backstage housing projection of the Great Hall blocks the morning sun), and the higher elevation of the Great Hall roof mitigates the visual impact the PV array has on the building. Refer to Appendix C for a "Schematic Roof Plan" of the Great Hall that depicts the PV array. Refer to Appendix C for Shadow Studies. The optimal angle of inclination of the solar panels for the latitude of Champaign, Illinois is considered to be approximately 34°. Line-type renderings showing the projection of the panels at 34 degrees inclination and 10 degrees inclination are included in this report for general comparison of visual impact. Ground level photo renderings are included for the 34° inclination of the PV array. Refer to Appendix E.

PV cells generate Direct Current (DC) that needs to be converted to Alternating Current (AC) for efficient distribution and compatibility with building power. The DC current from the panels could be routed to a centralized inverter, located somewhere within the facility, or alternatively, micro-inverters can be included with each of the PV panels, eliminating the interior space need for the central inverter. For purposes of this study, it appears that a central inverter could be located in one of the booths at the rear of the Great Hall if the central inverter configuration is chosen.

Roofing

Roofs at the Great Hall and theaters are fully adhered EPDM.

Facilities and Services has reviewed their records for the roofing of the Great Hall and reported that the roofing of the Great Hall was replaced by King Lar in 1995, and was covered by a 15 year (Firestone) warranty. Roofs of the Drama Theater and Music Theater were replaced in 1998 by Advanced Roofing. These roofs were also reportedly covered by 15 year Firestone warranties.

Facilities and Services has reported that there have been a number of leak calls on the roof of the Great Hall, reportedly due to the perimeter flashing details.

Given the age of the roofs, Facilities and Services has recommended that they be replaced prior to the installation of any rooftop PV array.

Configuration of the PV array and the chassis that supports it must provide a working vertical clearance between the roofing and the nearest components of the PV array. For purposes of the aesthetic assessment, this minimum clearance is taken as 12 in. between the top of the roofing and the supporting frame. Because of the 1:12 roof slope, this clearance increases linearly to approximately 33 in. at the east end of each panel frame assembly.

Lightning Protection

Currently the roof of the Great Hall is divided into an upper and lower area. The upper area of the roof currently has a lightning protection system. The lower area where the solar panels will be installed is not protected by a lightning protection system. With the installation of the new photo-voltaic panels it would be prudent to consider adding a lightning protection system to the roof to help protect the electronics from being damaged by surges from lightning strikes.

Structure

An assessment of the structural system is deferred to Phase 2 of this study. For purposes of cost assessment, a preliminary structural review of the roof structure was conducted. Based on this review, the framing system for the PV array has been conceptualized to deliver its load to the primary roof framing components (trusses), and not the secondary components (6 in. concrete roof deck and rolled steel beams). This general decision was reached in anticipation of limited capacities of the secondary components, and to minimize points of attachment for the structural frame.

Further structural evaluation, deferred to Phase 2, will assess the effects the PV panels will have on the total roof snow load due to snow drifting, and the structure's capability to sustain the weight of the panels, the support frames, and the additional snow load.

Noise and Vibration Analysis

An assessment of the acoustic impact the PV array may have on the facility is deferred until Phase 2 of the study. Preliminary considerations are that acoustics may be affected by transmission of vibration from wind and rain noise / vibration through the anchorage of the PV array to the building's primary structural system.

2. Codes and Permits

2.1 *Applicable Codes and Standards*

- University of Illinois Facilities and Services Standards for Design and Construction.
- ASCE 7-05 “Minimum Design Loads for Buildings and Other Structures.”
- Structural Loadings (gravity and wind) will need to be assessed per the International Building Code, 2009.
- Electrical design shall conform to the National Electrical Code (NEC) 2011.
- Code of Federal Regulations 29 CFR 1910 (pertaining to servicing of equipment near roof edges).
- 2012 International Fire Code (pertaining to maintenance of access to existing roof openings).

2.2 *Applicable Permits*

Should this project proceed to subsequent phases of investigation and design, configuration of the disconnect will need to be confirmed with the Electric Utility so that in cases of power outages the distribution network would not be back-fed by the PV array, thus energizing lines that would otherwise be thought to be de-energized. An additional protection to the manual disconnect switch is the inverter monitor’s normal power, and if it is lost, the inverter automatically disengages the system’s ability to back-feed power.

3. Site Requirements

Construction access for work on the Great Hall is expected to be gained via the east (Gregory Place) side of the facility. Laydown space and routing for deliveries is, at this time, thought to be achievable via the use of the plinth level immediately east of the Great Hall. At times, deliveries of equipment and materials may necessitate limitations on parking and pedestrian access from the Gregory Place side. Such limits (or shutdowns) would need to be coordinated around the scheduled activities at KCPA.

It is likely that a crane will be required to hoist components for the frame that will be constructed atop the roof to support the PV array. None of these components is expected to be extremely heavy (maybe on the order of 700 pounds for an individual steel beam, if it is concluded that the frame will indeed be steel-framed), but due to the required reach of the crane, a 165 ton all terrain crane is expected to be necessary for material hoisting. Refer to Appendix F for “Conceptual Crane Placement.”

Regular construction phase access for workmen and lighter material components and personnel to the roof of the Great Hall might be accomplished via a temporary construction stairway that could be installed somewhere along the east façade of the Great Hall. The benefits to the project of installing such a stairway are reduced travel time for the workmen to the roof, and a reduction of interruptions to the occupants of the facility.

This project is not expected to require any demolition, abandonments or relocations of utilities.

It is thought that the impacts of construction noise (crane engines, hammer drilling, concrete coring) on the functionality of the facility can be satisfactorily addressed by minimizing (or even prohibiting) such activities during performances and recordings. To achieve this objective, the contractor and KCPA administrators will need to agree to a work schedule, the general constraints of which should be defined in the bidding documents. For purposes of this study, some work activities are considered as being required to take place during non-standard working hours, and a 50 percent labor rate premium is included.

4. Maintenance Budget & Energy Budget for Sustainability

The PV array should require only minimal maintenance, and should have a service life of 20 to 25 years. This project should not result in an increase in the overall campus energy budget. On the contrary, this project should result in a reduction in the energy budget, as described within this report.

5. Design Concepts

Roof-mounted PV Array

A field investigation was conducted on Friday February 15, 2013. The focus of the investigation was to determine a suitable location for the electronics and panel-boards required for a new PV system and to observe the main electrical service room serving the Great Hall.

The current focus is to limit the location of new PV panels to the roof of the Great Hall only. Several factors went in to making this decision. From the perspective of electrical efficiency, a significant consideration is limiting, to the extent practicable, the number of three phase AC feeders that will need to be routed from the roof level of the building down to the lower level and connected into the main AC distribution system for the building. Currently the building's electrical power is served from four different locations. The existing service consists of primary metering and primary cabling routed underneath the building to four separate unit substations. Focusing on the Great Hall is considered to provide the maximum amount of solar generation, within the project budget, while minimizing dollars on other associated construction, such as running additional conduits and wiring.

Consideration has been given to the many types of inverter technologies for solar systems including; central inverter systems, string inverters and micro-inverters. Based on the limited amount of physical space near the roof level of the building and the difficulty in getting larger equipment to the upper level of the Great Hall, micro-inverters are recommended as a reasonable approach to this particular installation. A micro-inverter would be located at each photo-voltaic panel and the voltage is converted to AC right at the panel. The AC power will then be connected to a new power distribution panel in the upper level of the Krannert facility. The panel will then be tied back into the building main distribution system allowing power from the photo-voltaic array to be utilized to offset the building's electricity consumption.

Based on the project budget and preliminary evaluation, it has been preliminarily conceptualized that an 80 KW photo-voltaic system should be constructible on the facility. This is expected to consist of 320, 250-watt photo-voltaic panels. It is expected that the panels would fit on the lower portion of the roof of

the Great Hall as can be seen in the “Schematic Roof Plan – Great Hall” (Appendix C). A new 208Y/120VAC three phase 400A panel will need to be installed on the upper level of the Krannert facility in one of the existing rooms. A new feeder will then be routed down to the lower level of the building and tie into an existing main distribution panelboard. It is thought that the chase located near the southwest corner of the Great Hall can be used for cable rating.

A network communications cable will need to be installed to the location of the new panel at the upper level of the facility. A communications gateway then can be installed to monitor the specific energy generation of the system. This information can then be transported over the facility’s IP network and be displayed at a computer or Kiosk for convenient monitoring.

A basic non-project specific wiring diagram, example of a micro-inverter and a product data sheet for a typical solar panel are included in Appendix G.

Roof Access for Maintenance of the PV Array

Periodic access (every six to nine months) for maintenance of the PV array should be expected. This access would be facilitated if ladder and scuttle layout that accesses the west end of the roof of the Great Hall were reconfigured to allow a single ladder run from the Booth floor level to the roof. In its current configuration, personnel who access the roof of the Great Hall from the Booth level first pass through an opening in the ceiling. From just above the ceiling, they must then pass through a portal type opening to another floor from which a second ladder leads to the roof. This passageway is cumbersome and consideration should be given to improving it. It appears that shifting the roof hatch 3 to 4 ft to the south would provide for this direct access. This alternate location is shown on the conceptual roof plan layout of the PV array. The cost for this improvement is not included in the evaluation for this project, as it may be more appropriate to include this work with the separate roofing replacement project that would precede the PV installation

6. Opinion of Probable Construction Cost

The opinion of probable construction cost for the roof-mounted PV system, considering the difficulty level of the installation, is between seven dollars and twenty-five cents and seven dollars and fifty cents (\$7.25-\$7.50) per Watt. For an 80 KW (or 80,000 Watt) system the opinion of installed cost for the photo-voltaic system is summarized as follows:

Roofing Replacement	NOT IN PROJECT
Access and General Construction	\$128,000
Roof Scuttle improvements	NOT IN PROJECT
Electrical conduit / routing	\$117,000
PV cells and Micro-inverters	\$326,000
Electrical Power Distribution Equipment	\$10,000
Kiosk	\$4,000
TOTAL (excluding contingencies)	\$585,000

An allowance for shifting the roof scuttle to allow a single ladder run from the Booth level to the roof is not included in the Opinion of Probable Construction Cost (OPCC), but it is recommended that such an improvement be made to facilitate access to the roof.

It is recommended that the project be bid with alternates. For example the Base Bid could include a 60 KW system and there could be an alternate additive per unit bid for additional 10KW blocks.

Grants may be available to partially offset construction cost; however, identifying such grants is not within the scope of this study.

7 Payback Analysis

The payback analysis is included in Appendix B of this report. The analysis shows an estimated annual payback of around twelve thousand six hundred dollars (\$12,600) from energy savings on the five hundred eighty-five thousand dollar (\$585,000) initial investment for the roof-mounted PV array. No attempt has been made to assign a dollar value to the benefits of environmental stewardship. For comparison purposes, a ground-mounted PV array may be expected to have an annual payback of nineteen thousand dollars (\$19,000) on the same five hundred eighty-five thousand dollar (\$585,000) initial investment.

8. Project Schedule

A tentative project schedule will be identified during Phase 2 of the study. At this time, it is thought that on-site construction duration would be no more than eight weeks, assuming a construction schedule that would allow a 40 hour work week, of reasonable blocks of time. It is recognized that such working blocks of time may be limited to early morning, or night-time hours.


9. UIUC Review Comments

Refer to Appendix I.

Appendix A

Site Plan





1 SITE PLAN
NO SCALE:

© Copyright Hanson Professional Services Inc. 2013



SITE PLAN
UIUC PROJECT NUMBER: U12239
KRANNERT CENTER FOR THE PERFORMING ARTS
SOLAR PROJECT FEASIBILITY STUDY

11G0002I

A.1

Appendix B

Payback Analyses and
Opinion of Probable Construction Cost
for Roof Top Construction Activities



PAYBACK ANALYSES

AND

OPINION OF PROBABLE CONSTRUCTION COST

The Payback Analyses and Opinion of Probable Construction Cost (OPCC) prepared by Hanson Professional Services Inc. (Hanson) represent our best judgment as design professionals familiar with the construction industry. It should be recognized, however, that Hanson has no control over the cost of labor, materials or equipment, over the Contractor's methods of determining bid prices, over competitive bidding or market conditions, or over escalation in costs subsequent from the date of preparing these analyses and opinions of cost. Accordingly, Hanson cannot and does not guarantee that bids and actual payback will not vary from the opinions expressed herein.

The OPCC is based on Means 2013, first quarter for the Champaign-Urban area.

Payback Analysis for a Roof-Mounted Grid-Tied PV System in Illinois With No Incentives

INITIAL COSTS AND BENEFITS INITIAL SYSTEM COST

	Quantity	Unit Cost	Total
250 Watt Solar Panel (EA)	320	\$600	\$192,000
Structural Support System Installed with Labor (LS)	1	\$128,000	\$128,000
Micro Inverters and Connecting Wires (EA)	320	\$300	\$96,000
Disc. and Power Panels and Branch Circuits Installed with Labor (LS)	1	\$10,000	\$10,000
Monitoring System with Cat 6 Cabling Set Up and Programming (LS)	1	\$4,000	\$4,000
400 Amp Feeder: Conduit/Wire and Boxes Installed with Labor (LF)	600	\$175	\$105,000
Grounding wire Installed with Labor (LF)	600	\$20	\$12,000
Labor Solar Install 1.5 Hours per Panel (Hourly + OH&P)	475	\$80	\$38,000
Initial System Cost Total			\$585,000

System Cost after Basic Credits

Total			\$585,000
--------------	--	--	------------------

ANNUAL PRODUCTION

Number of Panels	320
STC Rating in Watts Per Panel	250
Total watts per hour assuming optimum conditions	80,000
Performance under typical solar conditions	80%
Adjusted watts per hour assuming real conditions	64,000
Average hours of sunlight per day	4.5
Estimated Watt Hours per day output	288,000
Estimated kilowatt hours per year	105,120
Illinois Electricity Rate	\$0.12
Estimated Income (Year 1)	\$12,614
Electrical Rate Annual Inflation Assumption	1.0%

REVENUES AND EXPENSES

	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025
Initial System Cost & Salvage Value	Year 0	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Year 11	Year 12
Electricity Sales		\$12,614	\$12,741	\$12,868	\$12,997	\$13,127	\$13,258	\$13,390	\$13,524	\$13,660	\$13,796	\$13,934	\$14,073
Cumulative Electricity Sales		\$12,614	\$25,355	\$38,223	\$51,220	\$64,346	\$77,604	\$90,994	\$104,519	\$118,178	\$131,975	\$145,909	\$159,982
Simple Payback (Personal) (Year cash flow turns positive):		(\$572,386)	(\$559,645)	(\$546,777)	(\$533,780)	(\$520,654)	(\$507,396)	(\$494,006)	(\$480,481)	(\$466,822)	(\$453,025)	(\$439,091)	(\$425,018)
	Year 13	Year 14	Year 15	Year 16	Year 17	Year 18	Year 19	Year 20	Year 21	Year 22	Year 23	Year 24	Year 25
	\$14,214	\$14,356	\$14,500	\$14,645	\$14,791	\$14,939	\$15,089	\$15,240	\$15,392	\$15,546	\$15,701	\$15,858	\$16,016
	\$174,196	\$188,553	\$203,053	\$217,698	\$232,489	\$247,428	\$262,517	\$277,757	\$293,148	\$308,694	\$324,396	\$340,254	\$356,266
	(\$410,804)	(\$396,447)	(\$381,947)	(\$367,302)	(\$352,511)	(\$337,572)	(\$322,483)	(\$307,243)	(\$291,852)	(\$276,306)	(\$260,604)	(\$244,746)	(\$228,733)

OPINION OF PROBABLE COST

PROJECT	Krannert PV Study	SUBMITTAL NO.	
LOCATION	Urbana, IL	TRADE	Gen_Struct
ARCHITECT	Hanson Professional Services Inc.	DATE	2/28/2013
ENGINEER	Hanson Professional Services Inc.		
PREPARED BY	R. Fiorito	PRICES BY	2013 RS Means
		CHECKED BY	G. Clack

Division Reference	Div. #	Description	QTY	UNIT	UNIT MAT'L	EXT. MAT'L	UNIT LABOR	EXT. LABOR	UNIT TOTAL INCL O&P	EXT. TOTAL INCL O&P
15419500600	15	Crane								
		Mobilization	1	LS					3000.00	3000.00
		Crane Time for PV Installation (OT)	16	Hr					505.00	8080.00
		Demobilization	1	LS					3000.00	3000.00
		Access Scaffolding Rent							277.00	
015423702250	01	Scaffolding	20	Ea	32.00	640.00			35.20	704.00
015423702900	01	Stair	10	Ea	40.00	400.00			44.00	440.00
Custom	01	Setup	8	Hr			180.00	1440.00	277.00	2216.00
15433403500	15	Light Plant	2	M					1724.80	3449.60
		Pipe Columns								
50519101430	05	Anchors	192	Ea	8.90	1708.80	24.00	4608.00	52.00	9984.00
		OT Installation	113	Hr			12.00	1356.00	16.83	1901.79
51223650450	05	Pipe Base Plate	33.12	SF	40.00	1324.80			44.00	1457.28
221113441400	22	Pipe Columns (Galvanized)	96	LF	41.00	3936.00			51.00	4896.00
51223171750		Erection	48	Ea			47.50	2280.00	59.07	2835.36
		OT Erection	48	Ea			23.75	1140.00	29.54	1417.92
		Wide Flange Dunnage								
51223751300	05	Wide Flange Framing	926	LF	55.13	51050.38	4.68	4333.68	70.71	65477.46
51223171100	05	Galvanizing	20372	LB	0.25	5093.00			0.28	5704.16
		OT Erection	926	LF			2.34	2166.84	2.69	2490.94
		Roofing Repairs								
Custom	07	EPDM Boot	48	Ea	15.00	720.00			20.00	960.00
	07	Insulation Repair	48	Ea	10.92	524.16			12.53	601.44
76523108200	07	Roof Repair	48	Ea	20.00	960.00	38.20	1833.60	84.35	4048.80
Custom		Asbestos Abatement	1	Ea					5000.00	5000.00
					MAT'L TOTAL	66357.14	LAB'R TOTAL	19158.12	TRADE TOTAL	127664.75

Payback Analysis for a Ground-Mounted Grid-Tied PV System in Illinois With No Incentives

		Quantity	Unit Cost	Total												
INITIAL COSTS AND BENEFITS																
INITIAL SYSTEM COST																
250 Watt Solar Panel (EA)		485	\$600	\$291,000												
Structural Support System Installed with Labor (LS)		1	\$89,000	\$89,000												
Micro Inverters and Connecting Wires (EA)		485	\$300	\$145,500												
Disc. and Power Panels and Branch Circuits Installed with Labor (LS)		1	\$10,400	\$10,400												
Monitoring System with Cat 6 Cabling Set Up and Programming (LS)		1	\$4,000	\$4,000												
800 Amp Feeder: Conduit Wire and Boxes Installed with Labor (LF)		50	\$300	\$15,000												
Grounding wire Installed with Labor (LF)		50	\$20	\$1,000												
Labor Solar Install: .75 Hours per Panel (Hourly + OH&P)		364	\$80	\$29,100												
Initial System Cost Total				\$585,000												
System Cost after Basic Credits				\$585,000												
Total				\$585,000												
ANNUAL PRODUCTION																
Number of Panels		485														
STC Rating in Watts Per Panel		250														
Total watts per hour assuming optimum conditions		121,250														
Performance under typical solar conditions		80%														
Adjusted watts per hour assuming real conditions		97,000														
Average hours of sunlight per day		4.5														
Estimated Watt Hours per day output		436,500														
Estimated kilowatt hours per year		159,323														
Illinois Electricity Rate		\$0.12														
Estimated Income (Year 1)		\$19,119														
Electrical Rate Annual Inflation Assumption		1.0%														
REVENUES AND EXPENSES																
Initial System Cost & Salvage Value																
Electricity Sales																
Cumulative Electricity Sales																
Simple Payback (Personal) (Year cash flow turns positive):																
		2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025		
		Year 0	Year 1	Year 2	Year 3	Year 4	Year 5	Year 6	Year 7	Year 8	Year 9	Year 10	Year 11	Year 12		
		(\$585,000)	\$19,119	\$19,310	\$19,503	\$19,698	\$19,895	\$20,094	\$20,295	\$20,498	\$20,703	\$20,910	\$21,119	\$21,330		
			\$19,119	\$38,429	\$57,932	\$77,630	\$97,525	\$117,619	\$137,913	\$158,411	\$179,114	\$200,024	\$221,143	\$242,473		
			(\$565,881)	(\$546,571)	(\$527,068)	(\$507,370)	(\$487,475)	(\$467,381)	(\$447,087)	(\$426,589)	(\$405,886)	(\$384,976)	(\$363,857)	(\$342,527)		
		2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037			
		Year 13	Year 14	Year 15	Year 16	Year 17	Year 18	Year 19	Year 20	Year 21	Year 22	Year 23	Year 24	Year 25		
		\$21,543	\$21,759	\$21,976	\$22,196	\$22,418	\$22,642	\$22,869	\$23,097	\$23,328	\$23,562	\$23,797	\$24,035	\$0		
		\$264,016	\$285,775	\$307,752	\$329,948	\$352,366	\$375,008	\$397,877	\$420,975	\$444,303	\$467,865	\$491,662	\$515,698	\$539,775		
		(\$320,984)	(\$299,225)	(\$277,248)	(\$255,052)	(\$232,634)	(\$209,992)	(\$187,123)	(\$164,025)	(\$140,697)	(\$117,135)	(\$93,338)	(\$69,302)	(\$45,225)		


Appendix C

Schematic Roof Plan – Great Hall




3/1/2013 10:35:06 AM

I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt



1 ROOF PLAN
 SCALE: 1/16" = 1'-0"




© Copyright Hanson Professional Services Inc. 2013	
SCHEMATIC ROOF PLAN - GREAT HALL	
UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
11G0002I	C.1

Appendix D

Shadow Studies



3/1/2013 10:36:13 AM
I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt




1 **SHADOW STUDY - JUNE 21, 2013; 10:00 AM**
PERSPECTIVE VIEW




© Copyright Hanson Professional Services Inc. 2013	
SHADOW STUDY - JUNE 21, 10 AM	
UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
11G0002I	D.1


3/1/2013 10:37:53 AM
I:\11jobs\11G0002\CAD\Render\Model\Kranmert Center.rvt



1 **SHADOW STUDY - JUNE 21, 2013; 4:00 PM**
PERSPECTIVE VIEW

 Hanson Professional Services Inc.	© Copyright Hanson Professional Services Inc. 2013	
	SHADOW STUDY - JUNE 21, 4 PM	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	D.2

3/1/2013 10:39:13 AM
I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt



1 **SHADOW STUDY - DECEMBER 21, 2013; 10:00 AM**
PERSPECTIVE VIEW



© Copyright Hanson Professional Services Inc. 2013


SHADOW STUDY - DECEMBER 21, 10 AM

UIUC PROJECT NUMBER: U12239
KRANNERT CENTER FOR THE PERFORMING ARTS
SOLAR PROJECT FEASIBILITY STUDY

11G0002I

D.3

3/1/2013 10:40:24 AM
I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt



1 **SHADOW STUDY - DECEMBER 21, 2013; 4:00 PM**
PERSPECTIVE VIEW



© Copyright Hanson Professional Services Inc. 2013

SHADOW STUDY - DECEMBER 21, 4 PM

UIUC PROJECT NUMBER: U12239
KRANNERT CENTER FOR THE PERFORMING ARTS
SOLAR PROJECT FEASIBILITY STUDY


11G0002I

D.4

Appendix E

Renderings – Line Type for Great Hall at
34° and 10° Inclination of Solar Panels and
Overall Ground Level Photo Renderings







1 NORTH CAMERA - 34° INCLINATION OF SOLAR PANELS
PERSPECTIVE VIEW - GREAT HALL ONLY FROM ILLINOIS STREET, LOOKING SOUTH

3/1/2013 1:05:00 PM
I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt


© Copyright Hanson Professional Services Inc. 2013


	PERSPECTIVE FROM NORTH - 34° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.1



1 SOUTH CAMERA -34° INCLINATION OF SOLAR PANELS
 PERSPECTIVE VIEW - GREAT HALL ONLY FROM OREGON STREET, LOOKING NORTH

© Copyright Hanson Professional Services Inc. 2013


 Hanson Professional Services Inc.	PERSPECTIVE FROM SOUTH - 34° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.2




① **EAST CAMERA - 34° INCLINATION OF SOLAR PANELS**
 PERSPECTIVE VIEW - GREAT HALL ONLY FROM 400 FT EAST OF GREGORY PLACE, LOOKING WEST


3/1/2013 1:29:28 PM I:\11jobs\11G0002\CAD\Render\Model\Kranmert Center.rvt


© Copyright Hanson Professional Services Inc. 2013

	PERSPECTIVE FROM WEST - 34° INCLINATION
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY
	11G0002I E.3



① NORTH CAMERA - 10° INCLINATION OF SOLAR PANELS
PERSPECTIVE VIEW - GREAT HALL ONLY FROM ILLINOIS STREET, LOOKING SOUTH


	PERSPECTIVE FROM NORTH - 10° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.4




① **SOUTH CAMERA -10° INCLINATION OF SOLAR PANELS**
PERSPECTIVE VIEW - GREAT HALL ONLY FROM OREGON STREET, LOOKING NORTH

3/1/2013 1:27:44 PM
I:\11jobs\11G0002\CAD\Render\Model\Kranert Center.rvt

© Copyright Hanson Professional Services Inc. 2013


	PERSPECTIVE FROM SOUTH - 10° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.5



① **EAST CAMERA - 10° INCLINATION OF SOLAR PANELS**
 PERSPECTIVE VIEW - GREAT HALL ONLY FROM 400 FT EAST OF GREGORY PLACE, LOOKING WEST

3/1/2013 1:31:57 PM
 I:\11jobs\11G0002\CAD\Render\Model\Kranmert Center.rvt


© Copyright Hanson Professional Services Inc. 2013


 Hanson Professional Services Inc.	PERSPECTIVE FROM WEST- 10° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.6



1 NORTH RENDERING 34° INCLINATION OF SOLAR PANELS
 NO SCALE:


© Copyright Hanson Professional Services Inc. 2013

	RENDERING FROM NORTH - 34° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.7



① **WEST RENDERING 34° INCLINATION OF SOLAR PANELS**
 NO SCALE:

3/1/2013 5:08:31 PM I:\11jobs\11G0002\CAD\Render\Model\Krannert Center.rvt


	© Copyright Hanson Professional Services Inc. 2013	
	RENDERING FROM WEST - 34° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.8



3/1/2013 4:47:09 PM I:\11jobs\11G0002\CAD\Render\Model\Krannert Center.rvt

1 EAST RENDERING 34° INCLINATION OF SOLAR PANELS
 NO SCALE:

© Copyright Hanson Professional Services Inc. 2013

	RENDERING FROM EAST - 34° INCLINATION	
	UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
	11G0002I	E.9

Appendix F

Conceptual Crane Placement





1 **CRANE PLACEMENT**
PERSPECTIVE VIEW

3/1/2013 2:39:27 PM
I:\1\jobs\11 G0002\CAD\Render\Model\Kranmert Center.rvt

© Copyright Hanson Professional Services Inc. 2013




CONCEPTUAL CRANE PLACEMENT	
UIUC PROJECT NUMBER: U12239 KRANNERT CENTER FOR THE PERFORMING ARTS SOLAR PROJECT FEASIBILITY STUDY	
11G0002I	F.1

Appendix G

Generic Wiring Diagram, Example of
Micro-inverter and Product Data Sheet
for Typical Photovoltaic Panel







The Enphase Energy Microinverter System improves energy harvest, increases reliability, and dramatically simplifies design, installation and management of solar power systems.

The Enphase System includes the microinverter, the Envoy Communications Gateway™, and Enlighten®, Enphase’s monitoring and analysis software.

PRODUCTIVE

- Maximum energy production
- Resilient to dust, debris and shading
- Performance monitoring per module

RELIABLE

- System availability greater than 99.8%
- No single point of system failure

SMART

- Quick and simple design, installation and management
- 24/7 monitoring and analysis

SAFE

- Low voltage DC
- Reduced fire risk



M215 — MICROINVERTER TECHNICAL DATA


Input Data (DC)		M215-60-2LL-S22/S23/S24 and M215-60-2LL-S22-NA/S23-NA (Ontario)	
Recommended input power (STC)	190 - 270W		
Maximum input DC voltage	45V		
Peak power tracking voltage	22V - 36V		
Operating range	16V - 36V		
Min./Max. start voltage	22V/45V		
Max. DC short circuit current	15A		
Max. input current	10.5A		
Output Data (AC)		@208 Vac	@240 Vac
Maximum output power	215W	215W	215W
Nominal output current	1.0A (arms at nominal duration)	0.9A (arms at nominal duration)	0.9A (arms at nominal duration)
Nominal voltage/range	208V/183-229V	240V/211-264V	240V/211-264V
Extended voltage/range	208V/179-232V	240V/206-269V	240V/206-269V
Nominal frequency/range	60.0/59.3-60.5 Hz	60.0/59.3-60.5 Hz	60.0/59.3-60.5 Hz
Extended frequency range	60.0/59.2-60.6 Hz	60.0/59.2-60.6 Hz	60.0/59.2-60.6 Hz
Power Factor	>0.95	>0.95	>0.95
Maximum units per 20A branch circuit	25 (three phase)	17 (single phase)	17 (single phase)
Maximum output fault current	1.05 Arms, over 3 cycles; 25.2 Apeak, 1.74ms duration		
Efficiency			
CEC weighted efficiency		96.0%	
Peak inverter efficiency		96.3%	
Static MPPT efficiency (weighted, reference EN50530)		99.6%	
Dynamic MPPT efficiency (fast irradiation changes, reference EN50530)		99.3%	
Night time power consumption		46mW	
Mechanical Data			
Ambient temperature range	-40°C to + 65°C		
Operating temperature range (internal)	-40°C to + 85°C		
Dimensions (WxHxD)	17.3 cm x 16.4 cm x 2.5 cm (6.8" x 6.45" x 1.0")*		
Weight	1.6 kg (3.5 lbs)		
Cooling	Natural convection - No fans		
Enclosure environmental rating	Outdoor - NEMA 6		
			* without mounting bracket
Features			
Compatibility	Pairs with most 60-cell PV modules		
Communication	Power line		
Warranty	25-year limited warranty		
Monitoring	Free lifetime monitoring via Enlighten software		
Compliance	UL1741/IEEE1547, FCC Part 15 Class B CAN/CSA-C22.2 NO. 0-M91, 0.4-04, and 107.1-01		

Enphase Energy, Inc.
 1420 N. McDowell Boulevard
 Petaluma, CA 94954
 P: 877-797-4743
info@enphaseenergy.com
<http://www.enphase.com>

142-00010, Rev 04b
 © 2012 Enphase Energy. All rights reserved.

Installing the Enphase Line Communications Filter (LCF)

LCFs are required at large installations that require more than one Envoy Communications Gateway™. Each Enphase LCF contains an Envoy and terminations for phase conductor lines in and out. By running phase conductors through the LCF, it filters power line communications and eliminates any potential inter-Envoy crosstalk in multi-Envoy installations.



Installation Considerations

1. The LCF services a maximum number of Enphase Microinverters per the following table, at a total continuous current of 100 Amps per phase.

208 VAC three-phase, approx 36 kW AC	Microinverters supported
M215-60	166
M190-72	189
M210-84	171
240 VAC single-phase, approx 24 kW AC	
M215-60	111
M190-72	126
M210-84	114

2. See the unit rating label for the compatible AC voltage requirements.
3. Use NEMA 4-rated, water-tight cable glands and hubs for all conduit entry. These must not compromise the integrity of the LCF's NEMA enclosure rating.
4. When determining the installation location for the LCF, account for conduit/cable entry for the bottom or side of the LCF enclosure.
5. Select wire size based on ampacity. At a minimum, you will need:
 - #2-#2/0 copper wire for L1, L2, L3 and neutrals
 - #8 AWG minimum for line grounding wire
 - CAT5E or equivalent for Ethernet
6. The LCF terminal blocks have AC fasteners that require compression to a specific torque value during installation. These terminal blocks connect the circuit conductors from PV load center and the grid load center. The terminal block screws must be set to the recommended torque values as specified by the terminal block manufacturer to securely fasten the conductors. See the following sections for wiring steps and for torque values. **Over-torquing the set screws can compromise the performance of the LCF.**
7. If you are using aluminum wire, use the specified procedure to install this wire. Refer to the terminal blocks for compatible gauge and wiring type.



DANGER: Risk of electrical shock. Adhere to all warnings and notes.
WARNING: Installation of the LCF must be done by a qualified electrician.
WARNING: Make sure that power is turned off from the utility and from the solar array before connecting the LCF.
WARNING: Ensure that all connections are torqued to values listed on the terminal block.
NOTE: Perform all wiring in accordance with the National Electric Code and ANSI/NFPA 70.
NOTE: Improper installation and/or maintenance of an LCF could result in reduced product reliability and/or damage to the product.
NOTE: The LCF must be installed between the utility-side circuit and the array-side circuit protection.
NOTE: Any changes or modifications to Enphase equipment not expressly approved by Enphase Energy could void the user's authority to operate this equipment.

1 Mount the LCF

1. Use the mounting holes on the back of the LCF enclosure for installation.
2. Remove all four hole seals and hang the LCF using 8mm mounting hardware with sealing washers.

2 Wire the LCF


1. De-energize all circuits before wiring the LCF.
2. Use antioxidant joint compound on all field termination connection points.
3. On the utility side, use cable ties to hold L1, L2 and L3 together. Allow offset for cable bending.
4. Remove the ferrite core from the assembly bag and slip it over the utility-side wire bundle.
5. Use a torque wrench and the specified hex bit to make the terminations in steps 6, 7 and 8.

Tighten the terminals to the torque values specified on the terminal blocks, according to conductor gauge and material. See table.

6. Terminate the utility-side lines to the terminal block labeled “Utility”.
 - For black terminal blocks, use a 3/16 wrench that is at least 1.25 inches long.
 - For grey terminal blocks, use both a 5mm wrench (at least 1.5 inches long) and a 6mm wrench (at least 1.25 long).
7. Terminate the neutral lines to the block labeled “Neutral” using an 8mm wrench that is at least 1 and 1/8 inches long.
8. Terminate the array-side lines to the terminal block labeled “Array”.
 - For black terminal blocks, use a 3/16 wrench that is at least 1.25 inches long.
 - For grey terminal blocks, use both a 5mm wrench (at least 1.5 inches long) and a 6mm wrench (at least 1.25 long).
9. Route the ground wires through the LCF so that they make contact with all hubs and connect them to the ground bus using an approved grounding connection method.

10. Use a 1/2 inch knockout set to create a conduit knockout on the left side of the enclosure, and pass the CAT5E through the knockout.
11. If needed, to allow the CAT5E to pass through the strain relief, cut and reterminate the CAT5E.
12. Connect the one end of the CAT5E to the Envoy, and connect the other end to the broadband router.
13. After 30 minutes, retighten all terminations to the appropriate torque value. **Do not over-torque.**


Terminal Block Types & Torque Specifications



Marathon Black (Line)



Marathon Grey (Line)



Ferraz Shawmut (Neutral)

Conductor gauge	Terminal block type and torque specifications		
	Marathon Black (Line)	Ferraz Shawmut (Neutral)	Marathon Grey (Line)
#2/0 - #6	120 lbf-in	---	---
#2/0 - #1	---	100 lbf-in	120 lbf-in
#2 - #6	---	80 lbf-in	80 lbf-in
#8	40 lbf-in	60 lbf-in	40 lbf-in

3 Turn Up the LCF

All system diagnostics are performed using a Internet-connected computer or laptop and the Envoy. Prior to turn up, ensure that all AC wiring is complete and that the Ethernet connection is complete to the Envoy.

Refer to the *Envoy Communications Gateway Installation and Operation Manual* for more information on the Envoy.


1. Energize the system at the utility side.
2. Energize all the array-side circuit breakers.
3. Flip the blue switch on (to the right of the neutral block) inside the LCF. This breaker protects the Envoy.
4. Ensure the Envoy starts up. The LCD screen will be active.

Periodic Maintenance

During regular scheduled maintenance of the PV system, do the following:

1. De-energize or disconnect all circuits before working with the LCF.
2. Check the terminal blocks for proper torque. The torque values of each terminal block should be checked for compliance with the torque requirements listed on the terminal block.
3. Periodically check that the integrity of the enclosure and all internal connections are not compromised.

LCF Wiring Diagram





250 / 6 MH PHOTOVOLTAIC MODULE

Three Full Decades of Power - Guaranteed

- > With our 30-Year, 80% Power Guarantee, you can be assured top-production for 3 decades
- > Industry leading 12 Year, 90% Power Guarantee

High Efficiency Modules when Value Matters Most

- > Only positive tolerances of up to +5 watts ensure maximum power without compromise
- > Simple compatibility with any of our inverter partner products to achieve maximum system output

Quality Tested, Service Assured

- > Certified by the most rigorous US and International standards
- > 10-Year Product Warranty
- > Built to withstand even the most harsh conditions

Flexible Design

- > Ideal for all rooftops and ground mount installations
- > Easily connected to the grid or used in off-grid scenarios
- > Suitable for use on ungrounded PV arrays
- > Allows for string size up to 1000 V, which can reduce cost



Number of Cells: 60
 Solar Cell Type: monocrystalline
 Power class: 250 Wp

30	YEAR 80% POWER GUARANTEE	12	YEAR 90% POWER GUARANTEE	10	YEAR PRODUCT WARRANTY	+5	WATTS POSITIVE TOLERANCES
----	--------------------------	----	--------------------------	----	-----------------------	----	---------------------------

ELECTRICAL CHARACTERISTICS*

Maximum Power Rating	P_{mp} (W)	250
Tolerance of P_{mp}	(W)	-0/+5
Maximum Power Voltage of P_{mp}	V_{mp} (V)	30.40
Maximum Power Current P_{mp}	I_{mp} (A)	8.22
Open Circuit Voltage	V_{OC} (V)	37.51
Short Circuit Current	I_{SC} (A)	8.88
Maximum System Voltage	(V)	1000
Maximum Series Fuse	(A)	15


* STC @ 25° C, 1000 W/m², AM 1.5

TECHNICAL FACTS

Number of Cells (Matrix)	60 (6 x 10)
Solar Cell Type	monocrystalline
Solar Cell Size (mm)	156 x 156
Solar Cell Size (in)	6 x 6
Dimensions (L x W x H mm)	1636 x 992 x 45
Dimensions (L x W x H in)	64.41 x 39.06 x 1.77
Weight (kg)	19.5
Weight (lbs)	43.0
Module Efficiency (%)	15.4
Connector Type	MC4 or equivalent

THERMAL CHARACTERISTICS

NOCT	(°C)	+ 45 ±3
Temperature Coefficient	I_{SC} (%/°C)	+ 0.047
Temperature Coefficient	V_{OC} (%/°C)	- 0.31
Temperature Coefficient	P_{mp} (%/°C)	- 0.41



61215
61730



MAGE SOLAR USA

720 Industrial Boulevard · Dublin, Georgia 31021 USA

Toll-free (877) 311-6243 · Main Office (478) 609-6640 · Fax (478) 275-7685

info@pagesolar.com · www.pagesolar.com

© MAGE SOLAR PROJECTS, INC. · 1/2013 · All rights reserved. Specifications included in this datasheet are subject to change without notice. Products may not be applicable for all areas. Image may not represent actual module.

Appendix H

Electrochromic Glazing Evaluation
for Great Hall



H. Electrochromic Glazing Evaluation for Great Hall

The original glazing used in the west curtain wall of Krannert's Great Hall was made of single pane 1/4 in. clear glass. As part of the photovoltaic study, Hanson was asked to provide energy savings calculations associated with replacing this glass with electrochromic glazing. Hanson used eQuest v3.64 to simulate the existing space generally defined as the Great Hall Foyer with two alternative curtain wall glazing systems. The baseline simulation uses the existing single pane glass. The alternative curtain wall glazing systems modeled were Double Pane Low-E Electrochromic and standard Double Pane Low-E. The standard Double Pane Low-E glass was modeled for the sake of comparison because it was apparent that most of the energy saving resulted from the upgrade to double pane Low-E glass and not from the use of Electrochromic glazing.

The UIUC FY2013 variable cost utility rates were used for the analysis as shown in Table H1.1.

Table H1.1 Utility Rates: UIUC FY 2013 Variable Rates

<i>Utility</i>	<i>Rate</i>
Campus Steam	\$8.29 per klbs
Campus Chilled Water	\$9.89 per Million Btu

The results of the simulation are summarized in Table H1.2.

Table H1.2 Energy Savings and Cost Results Summary⁽¹⁾

	<i>Annual Heating Savings (klb steam)</i>	<i>Annual Cooling Savings (MBtu Chilled Water)</i>	<i>Annual Heating Savings (\$ (2))</i>	<i>Annual Cooling Savings (\$ (2))</i>	<i>Total Annual Energy Cost Savings (\$ (2))</i>
Double Pane Low-E	344	2	\$2,855	\$18	\$2,873
Double Pane Low-E Electrochromic	322	154	\$2,675	\$1,521	\$4,196

- Savings shown are in comparison to 1/4 in. single pane clear glass.*
- These projected savings are derived from a reduction of energy consumption based on building geometry, construction type, internal loads, assumed use schedules, and average annual weather data. While those results are shown to the nearest \$1, they should be considered approximate and for general comparison only.*

The results shown in Table H1.2 indicate that the annual energy cost savings associated with replacing the curtain wall with Double Pane Low-E Electrochromic glazing would be \$4,196, a substantial portion of which is attributed to the heating savings of upgrading the single pane glass to double pane Low-E glass. The net energy cost savings associated with adding an electrochromic feature to a clear double pane low-E glazing for the great hall foyer at Krannert is therefore estimated to be one thousand three hundred twenty-three dollars (\$1,323) [\$4,196 - \$2,873] per year.

Excitons by 11 Single Pane Clear

MONTH	C O O L I N G				H E A T I N G				E L E C			
	COOLING ENERGY (MBTU)	TIME OF MAX DY HR	DRY-BULB TEMP	WET-BULB TEMP	MAXIMUM COOLING LOAD (KBTU/HR)	HEATING ENERGY (MBTU)	TIME OF MAX DY HR	DRY-BULB TEMP	WET-BULB TEMP	MAXIMUM HEATING LOAD (KBTU/HR)	ELECTRICAL ENERGY (KWH)	MAXIMUM ELEC LOAD (KW)
JAN	0.00000	0	0.F	0.F	0.000	-268.675	30	-5.F	-6.F	-714.325	5858.	14.704
FEB	0.00000	0	0.F	0.F	0.000	-219.700	6	-4.F	-5.F	-650.644	5291.	14.704
MAR	0.83823	31	64.F	48.F	102.155	-144.789	7	15.F	13.F	-449.965	5858.	14.704
APR	16.14105	28	84.F	74.F	300.262	-62.626	2	32.F	32.F	-319.696	5669.	14.704
MAY	48.20464	29	89.F	69.F	353.650	-21.938	11	40.F	37.F	-233.952	5858.	14.704
JUN	83.16296	28	88.F	74.F	362.853	-0.370	18	54.F	49.F	-40.102	5669.	14.704
JUL	101.88153	13	91.F	74.F	392.114	-0.241	3	55.F	52.F	-32.458	5858.	14.704
AUG	90.46751	26	90.F	78.F	385.105	-0.524	7	51.F	50.F	-48.513	5858.	14.704
SEP	58.63651	4	92.F	78.F	402.117	-11.826	24	38.F	38.F	-196.789	5669.	14.704
OCT	10.11323	11	80.F	62.F	161.196	-53.299	21	35.F	31.F	-255.420	5858.	14.704
NOV	0.25781	3	69.F	59.F	51.151	-130.834	28	27.F	24.F	-379.733	5669.	14.704
DEC	0.00000	0	0.F	0.F	0.000	-234.930	28	-4.F	-5.F	-595.051	5858.	14.704
TOTAL	409.703				-1149.753					-714.325	68974.	14.704
MAX					402.117							

New Double Pane Electrolux

Krannert PV Study

DOE-2.2-47h2 8/23/2013 16:43:20 BDL RUN 5

REPORT- LS-D Building Monthly Loads Summary

WEATHER FILE- Springfield IL TMY2

MONTH	C O O L I N G				H E A T I N G				E L E C			
	COOLING ENERGY (MBTU)	TIME OF MAX DY HR	DRY-BULB TEMP	WET-BULB TEMP	MAXIMUM COOLING LOAD (KBTU/HR)	HEATING ENERGY (MBTU)	TIME OF MAX DY HR	DRY-BULB TEMP	WET-BULB TEMP	MAXIMUM HEATING LOAD (KBTU/HR)	ELEC-TRICAL ENERGY (KWH)	MAXIMUM ELEC LOAD (KW)
JAN	0.00000	0	0.F	0.F	0.000	-191.216	30	-5.F	-6.F	-510.753	5858.	14.704
FEB	0.00000	0	0.F	0.F	0.000	-158.199	6	-4.F	-5.F	-470.884	5291.	14.704
MAR	0.19992	31	64.F	48.F	36.948	-105.976	9	14.F	12.F	-335.360	5858.	14.704
APR	8.31075	28	84.F	74.F	173.472	-46.585	2	32.F	32.F	-223.690	5669.	14.704
MAY	28.11726	29	89.F	69.F	214.472	-16.932	11	40.F	37.F	-168.942	5858.	14.704
JUN	52.18403	28	88.F	74.F	221.108	-0.442	18	54.F	49.F	-34.640	5669.	14.704
JUL	65.91494	13	91.F	74.F	242.429	-0.278	3	55.F	52.F	-30.972	5858.	14.704
AUG	58.25732	27	92.F	80.F	238.999	-0.581	7	51.F	50.F	-45.526	5858.	14.704
SEP	37.57512	4	92.F	78.F	252.063	-9.273	24	38.F	38.F	-151.853	5669.	14.704
OCT	5.27904	30	76.F	68.F	89.193	-39.786	2	29.F	27.F	-194.003	5858.	14.704
NOV	0.03196	3	69.F	59.F	13.774	-92.033	21	21.F	20.F	-275.300	5669.	14.704
DEC	0.00000	0	0.F	0.F	0.000	-165.788	13	4.F	3.F	-413.663	5858.	14.704
TOTAL	255.870					-827.087					68974.	
MAX					252.063					-510.753		14.704

Appendix I

UIUC Review Comments



Project Review

Krannert Solar Study

Architectural Review Comments

Plan Reviewer:		McClure	
Comment Number	Drawing or Spec Reference	UIUC Facilities & Services Comment	AE Response
Drawing Comments			
Specification Comments			
101	Regarding access to the roof top for workers	Page 7 mentions a temporary construction stairway on the east side of the building. What is the height from the plaza deck level to the roof top? Would a buck hoist better serve the project? What would that add to the cost?	Building height is 60 ft from the plaza level to the roof at the east end of the building. We looked into a buckhoist and the cost was considered to be prohibitive - around \$25,000 for installation, rental and removal.
102	Regarding the Pythagoras Solar Glass	The literature says they have teamed up with "a number of leading glass manufacturers". Which ones?	We can evaluate this further in Phase 2 if the study is so-directed. Other reviewers have commented that the PVGU should not be included in this study
103		When Heat Mirror came on the market it sounded like a great idea. UI experience with it at ACES Library was that in less than 8 years, every piece of the glass had a failed seal in the air space. Some pieces failed within the first year. What assurances are there that this will not happen with the PV's in the middle? How are they inserted and held in the air space? Will they have a potentially adverse impact on the seal?	ditto
104		What does the product cost? Replacement cost for damaged pieces of glass is always a concern for us.	ditto
105		So the Student Sustainability Committee may pay for the installation. What if the product fails? Who will pay to remove the PV glass and re-install regular glass?	UIUC would need to assess how such costs would be borne if outside the manufacturer's warranty period

Plan Reviewer: John Prince

Comment Number	Drawing or Spec Reference	UIUC Facilities & Services Comment	AE Response
Drawing Comments			
Specification Comments			
	Page 3-4	The Executive Summary is in conflict with the project description. The description called for a study on the use of electro-chromatic glazing on the west wall and its effect on the thermal loading and energy consumption in the Great Hall area. The study only made passing references to photovoltaic glass units and included no analysis. An acceptable submittal must include this requested analysis which was not included in this report. Payback analysis should be both for the replacement and the increased cost of the electro-chromatic system over standard insulated glass units.	Hanson understood the study's focus to be directed to evaluation of capturing of solar energy. The Project's Executive Summary included in the Scope Statement references electro chromic <u>or thin film solar</u> on the west wall of the Great Hall as part of the overall solar energy project. In accordance with discussions at the kick-off meeting, our evaluation was limited to consideration of photovoltaics (thin film solar), and assessment of potentially offsetting HVAC demands through tinting of the glazing on the west curtain wall was not understood to be within the scope of the study.
	Page 9	The Photovoltaic Glass evaluation was NOT part of the requested study and should be deleted from this report.	All reference to the PV glazing units can be removed in their entirety if the AE is so directed by UIUC

Plan Reviewer:		Craig Grant	Response by G. Clack (Hanson)
Comment Number	Drawing or Spec Reference	UIUC Facilities & Services Comment	AE Response
Drawing Comments			
1	Page 10	the statement that "the roof scuttle improvements and the roofing replacement are not in the opinion of probable cost is not helpful since the access modifications will be required for any such solar panel placement and the roofing costs would be important to determine the viability of this project. It does no service to the campus to separate these issues from the solar panel installation cost analysis.	The understood, primary intention of Phase 1 of this study was aesthetic evaluation of the PV installation. It has been opined by Facilities and Services that roofing is nearing the end of its useful life, and it was assumed by Hanson that roofing replacement would be funded separately. The cost of roofing replacement and installation of a new scuttle can be evaluated in the second phase of the study if the decision is made by the University to proceed with Phase 2. The payback analysis, without the cost of a roofing replacement project, does not seem to be attractive as it stands, and adding roofing replacement costs will make the payback even less attractive.

Krannert Center for the
Performing Arts

Solar Project Feasibility Study

**University of Illinois
at Urbana-Champaign**

Project Number: U12239

Phase 2

95% Submittal

March 25, 2014

Table of Contents

EXECUTIVE SUMMARY (PHASE 2)	3
1. STRUCTURAL EVALUATION	4
1.1 Description.....	4
1.2 Evaluation of Roof Trusses Under Current Loadings	4
1.3 Evaluation of Roof Trusses Under Loadings Imposed by Photovoltaic Array.....	5
1.4 Roof Truss Strengthening Concept	6
2. ROOFING REPLACEMENT	7
3. ROOF SCUTTLE IMPROVEMENTS	7
4. NOISE AND VIBRATION ANALYSIS	7
5. COMPARISON OF POWER GENERATION BETWEEN 10 DEGREE AND 34 DEGREE INCLINATION ANGLE OF PV ARRAY	7
6. OPINION OF PROBABLE CONSTRUCTION COST	8
7 PAYBACK ANALYSIS	8
8. PROJECT SCHEDULE	9

Appendices

Appendix A – Selected Structural Drawings from 1966 Plans by Lev Zetlin

Appendix B – Kirkegaard Report – Noise and Vibration Analysis

Appendix C – Opinion of Probable Construction Cost – General Work

Copyright © 2012 by Hanson Professional Services Inc. All rights reserved. This document is intended solely for the individual or the entity to which it is addressed. The information contained in this document shall not be duplicated, stored electronically, or distributed, in whole or in part, by anyone other than the recipient without the express written permission of Hanson Professional Services Inc., 1525 S. Sixth St., Springfield, IL 62703, (217) 788-2450, www.hanson-inc.com. Unauthorized reproduction or transmission of any part of this document is a violation of federal law. Any concepts, designs and project approaches contained herein are considered proprietary. Any use of these concepts and approaches by others is considered a violation of copyright law.

Executive Summary (Phase 2)

The purpose of the study is to examine the feasibility of installing a solar photovoltaic (PV) system on one or more of the roofs at Krannert Center for the Performing Arts (KCPA). The study was divided into two phases.

Phase 1 of the study presented an assessment of the visual impact on the facility, an opinion of probable construction cost (OPCC), general considerations of construction phasing and associated general construction, and a simple payback analysis for the PV array.

Phase 2 of the study, presented herein, further examines:

- the capacity of the existing roof structure, and presents a conceptual level opinion of construction cost for roof strengthening;
- cost of roofing replacement;
- concept and opinion of cost for improving maintenance access to the roof;
- noise and vibration analysis associated with mounting a photovoltaic array on the roof of the Great Hall;
- general comparison of power generation efficiency between a 10 degree and 34 degree angle of inclination; and
- an updated OPCC.

The Phase 2 assessment has identified deficiencies in the existing roof structure that will need to be addressed prior to the addition of any new loads. General strengthening concepts are described in this report, and a high level OPCC for this roof strengthening is presented.

Kirkegaard Associates prepared a general assessment of noise and vibration considerations that should be addressed in the design, and their report is included in Appendix B.

The OPCC presented in this Phase 2 of the report includes only the items described above. A recapitulation of costs identified during Phase 1 and Phase 2 are presented in the Summary Report.

1. Structural Evaluation

1.1 Description

Phase 2 of the feasibility study included a structural analysis of the existing roof trusses and slabs and the impact of placing photovoltaic cells on the roof structure.

Two options for supporting the PV cells were considered. The first was a steel support system. Vertical steel posts would be secured to the existing structure and would support the framing that holds the PV cells. The second option considered vertical concrete knee walls aligned with the trusses that would support the PV cell frames. An acoustical assessment determined that steel supports may more directly transfer wind and other environmental loads to the roof steel. This could potentially exacerbate vibration and noise transmission through the building's interior. For this reason, the loading of the heavier concrete walls was considered for structural analysis purposes.


1.2 Evaluation of Roof Trusses Under Current Loadings

The existing structure was assessed based on the original 1966 drawings prepared by Lev Zetlin and Associates (see Appendix A). The current roof structure consists of a 6 in. reinforced concrete slab supported by steel trusses that span 84 ft across the Great Hall. The trusses are made up of tee-shaped chord members and double-angle web members. Secondary wide flange beams spaced at approximately 21 ft span between the trusses and create two-way action in the slab. Analyses conducted during Phase 1 of this Feasibility Study showed that the secondary components (roof slab and beams) do not have sufficient capacity to support the added load of the photovoltaic array. Consequently, support systems were conceptualized that would deliver the new loads directly to the trusses. Analyses conducted during Phase 2 therefore focused on the roof trusses.

Loads and stresses on the trusses were determined using the American Society of Civil Engineers (ASCE) 7-10 design loads and typical material weights. Taking into consideration the dead loads (truss members, roofing materials, concrete slab, catwalks, and ceilings) and snow loads, the total load on the roof structure is estimated to be 130 lbs per sq. ft (see table below). With a distance of 21 ft-4 in. between trusses, this equates to approximately 2,800 lbs per lineal foot applied to the truss.

Existing Load Summary	Load (lb/ft ²)
Truss (Self)	10
Slab	75
Catwalks and Ceilings	13
EPDM Roof	5
Insulation	3
<u>Live Loads (Snow)</u>	<u>25</u>
Total	131 lb/ft²

Using structural analysis software and hand calculations, it was determined that the members of the existing roof trusses labeled T-3 in the original drawings do not meet the current structural steel code for compression capacity under these load conditions. At the time of original construction, the members met requirements called for by the applicable code, the American Institute of Steel Construction (AISC) 6th Edition Steel Construction Manual. The AISC Steel Construction Manual has since been updated to account for torsional and flexural-torsional buckling and strength limitations of slender elements within members. The red in the figure below indicates those members of the T-3 trusses that are overstressed under current conditions, without the addition of any new loads, when evaluated according to the 14th Edition of the AISC Steel Construction Manual.




1.3 Evaluation of Roof Trusses Under Loadings Imposed by Photovoltaic Array

The trusses were also analyzed for the addition of the PV cells and accompanying concrete knee walls. The weights of these materials and associated snow drifting loads would apply an additional 30 lbs per sq. ft (see table below), or approximately 665 lbs per lin. ft to the T-3 trusses at the locations of the new walls.

Additional Load Summary	Load (lb/ft ²)
Concrete Wall	18.75
Photovoltaic Cells	5
<u>Snow Drift</u>	<u>7</u>
Total	31 lb/ft²

These loads would introduce an additional sixty thousand pounds (approximate) into each of the steel chord members, causing four additional chord members to be stressed beyond code-prescribed limitations, as indicated in blue in the figure below.



1.4 Roof Truss Strengthening Concept

Two concepts for strengthening the truss top chord members were considered. Both are anticipated to be complex to execute due to the access constraints.

The first concept for strengthening these members involves welding 7/8 in. x 9 in. steel plates to the stems of the tee-shaped chord elements. These plates would increase the compressive strength of the current members such that they would meet the provisions of the current AISC Steel Construction Manual.

The second concept for strengthening the trusses would be to post-tension the top and bottom chords of the trusses. Steel cables would run approximately between the 1/4 and 3/4 points of the bottom chord of the truss and then turn and run diagonally towards the top chord bearing points. The cables would be anchored into the top chords and tensioned via a jacking system that would reduce the compression in the top chord and reduce tension in the bottom chord, offsetting the design loads and lowering the stresses experienced by the members to within code-prescribed limitations. This method may reduce the number of points of access required for repair, which may in turn decrease the cost of work as compared to welding plates across the entire chord length.

Because the ceiling of the Great Hall is expected to prevent direct access to the trusses from the Great Hall, any scaffolding built would have to be suspended from the trusses. Given the complex nature of this work, the cost of strengthening the trusses could be in a range between two hundred thousand dollars (\$200,000) and three hundred thousand dollars (\$300,000).

2. Roofing Replacement

During Phase 1 of the study it was identified that the roofing of the Great Hall should be replaced prior to the installation of the photovoltaic array. Drawings detailing the current roof system installed in 1995 were not available for Hanson's review, and a detailed examination of the roofing will need to be done to determine the extent of replacement needs. For planning purposes, an overall removal and replacement of all flashing, roofing materials, and insulation was considered. An OPCC for this scope of roofing work is approximately twenty dollars (\$20) per sq. ft of roof, resulting in an OPCC of three hundred sixty thousand dollars (\$360,000) for roofing work at this section of the facility.

3. Roof Scuttle Improvements

As identified in Phase 1 of this study, access to the roof is cumbersome and consideration should be given to improving it. It appears that shifting the roof hatch 3 to 4 ft to the south would provide for this direct access. This alternate location is shown on the conceptual roof plan layout of the PV array.

Modifications would involve constructing a new opening through the roof structure, in-filling the existing opening, and constructing a new ladder from the Booth Level to the roof in alignment with the new roof hatch. Installation of a safety post that could be extended above the hatch when in use is also recommended.

An OPCC for these modifications is fifteen thousand dollars (\$15,000). Note that the cost of roof flashing is not considered in this item, as it is accounted for separately under "Roofing Replacement."

4. Noise and Vibration Analysis

Kirkegaard Associates has conducted a general assessment of the potential for noise and vibration disruptions that may result in the Great Hall due to the placement of a roof-mounted photovoltaic array. Kirkegaard's report is included as Appendix B. General recommendations for decoupling the PV array from the roof structure are presented.

The need for additional evaluation is also identified in Kirkegaard's report. Kirkegaard's report includes unit costs associated with potential noise and vibration options. Costs for the spring isolator system are compiled in the "General Structural" OPCC.

5. Comparison of Power Generation between 10 degree and 34 degree Inclination Angle of PV Array

The angle of inclination for photovoltaic cells that is recommended for optimizing generation of electricity is based on the location with respect to the earth's latitude. For this location, the

recommended fixed angle of inclination is approximately 34 degrees. Due to aesthetic objectives to limit the visible projection of the photovoltaic array, it is recommended that the angle of inclination be no more than 10 degrees. The loss of electrical generation efficiency between an angle of inclination of 34 degrees (optimum) and 10 degrees (chosen for aesthetics) is approximately 7 percent.

6. Opinion of Probable Construction Cost

An OPCC is included in Phase 1 of the study. However, the OPCC prepared during Phase 1 did not include the cost of truss strengthening, roofing replacement or the cost of modifying the roof access hatch (roof scuttle). The costs presented in the Phase 1 study are included herein for reference. Modifications and additional items are summarized in the Phase 2 column, and those items for which there is no change are carried over as such into the Phase 2 column. These costs are presented below, and a recapitulation of cost is included in the Summary Report. An itemized OPCC for the General Work is included in Appendix C.

ITEM	Phase 1 OPCC	Phase 2 OPCC
Roofing Replacement	Not included	\$360,000
Construction Access and General Construction	\$128,000	\$132,000
Roof Scuttle Improvements	Not included	\$15,000
Roof Truss Strengthening	Not included	\$300,000
Noise and Vibration Mitigation	Not included	\$36,000
Electrical conduit / routing	\$117,000	\$117,000
PV cells and Micro-inverters	\$326,000	\$326,000
Electrical Power Distribution Equipment	\$10,000	\$10,000
Kiosk	\$4,000	\$4,000
TOTAL (excluding contingencies)	\$585,000	\$1,300,000

7. Payback Analysis

The payback analysis is included in Appendix B of the Phase 1 report. The analysis shows an estimated annual payback (value of generated electricity) of around twelve thousand six hundred dollars (\$12,600). The payback period is difficult to assess given the varied nature of collateral work associated with this project. No attempt has been made to assign a dollar value to the benefits of environmental stewardship.

For comparison purposes, a ground-mounted PV array may be expected to have an annual payback of nineteen thousand dollars (\$19,000) on the same five hundred eighty-five thousand dollar (\$585,000) initial investment.


8. Project Schedule

During Phase 1 of the study, it was expressed that on-site construction duration would be no more than eight weeks, assuming a construction schedule that would allow a 40 hour work week, of reasonable blocks of time. Given the additional items of work that were identified during Phase 2, it is recommended that this be increased to no less than 12 weeks.

Appendix A

Selected Structural Drawings
from 1966 Plans by Lev Zetlin





T-3 truss detail taken from drawings prepared by Lev Zetlin and Associates.

Appendix B

Kirkegaard Report -
Noise and Vibration Analysis



SOLAR PROJECT FEASIBILITY STUDY - PHASE II

Krannert Center for the Performing Arts, University of Illinois at Urbana-Champaign

Noise and Vibration Analysis

March 24, 2014



EXECUTIVE SUMMARY

As part of the Solar Project Feasibility Study, Kirkegaard Associates (Kirkegaard) considered the acoustic impact of installing a solar photovoltaic (PV) system on the roof of the Krannert Center for the Performing Arts (KCPA) at the University of Illinois at Urbana-Champaign.

Opened in 1969, Foellinger Great Hall is the crown jewel of the KPCA. The 2,100 seat hall is loved for its excellent acoustics and was designed by noted acoustician, Dr. Cyril Harris. The hall is the main venue for the Champaign-Urbana Symphony Orchestra, Sinfonia da Camera and the University of Illinois Wind Symphony. The hall has also hosted world-renowned visiting orchestras including the Chicago Symphony and the Sydney Symphony.

This study aims to discuss the potential acoustic issues and proposed solutions related to locating the PV system directly above the Great Hall.

EXISTING CONDITIONS

The original roof construction in 1969 consisted of long span trusses supporting a 6" thick concrete roof slab. Rigid insulation with a stone ballasted built-up roof membrane was constructed on top of the concrete to form the water and thermal barrier. The ceiling of the Great Hall is a heavy plaster construction suspended from the roof slab. The interstitial space created between the bottom of the concrete slab and plaster ceiling is the attic space above the Great Hall. This construction along with the deep airspace of the attic combined to make for an excellent noise barrier to the exterior. The roof ballast also served a dual purpose in that it dissipated the impact noise of heavy rains and hail.

In 1978, the roof membrane above the Great Hall was replaced with a single-ply roof membrane. This roofing system is fully adhered and requires no stone roof ballast to hold the membrane in place and protect it against ultraviolet light. From an acoustics perspective the benefit of dissipation of rain and hail that the original ballast provided is no longer present. To our knowledge, however, there have been no complaints from the user groups of noise since the roof replacement.

NOISE AND VIBRATION ANALYSIS

This study proposes the installation of a PV system over a large area of the roof above the Great Hall's seating chamber. The layout of the PV cells on the roof aims to maximize the sun exposure and minimize the aesthetic impact to the building's sightlines. Refer to Phase 1, Appendix C, Schematic Roof Plan – Great Hall.

The objective from an acoustic isolation perspective is to identify potential detriments to the acoustic environment that might be caused by the installation of the PV system and consider details of construction that could be implemented to mitigate such detriments to the Great Hall. Airborne sound and the structure-borne sound issues are both addressed in this study. Airborne sound is typically generated by airplanes, equipment, machinery,

automobiles, etc. that is transmitted through the building elements – walls, floors, roof structure into the Great Hall. Structure-borne sound is produced by an impact of the building element. The impact causes the elements to vibrate, and as they vibrate, they radiate sound. It is our understanding that neither is an issue with the current roof construction.

With respect to airborne sound the overall construction as described above is not changing so airborne noise should not increase or decrease due to the PV system installation.

With respect to structure-borne sound there is a concern that the large areas of the PV panels exposed to the impact from heavy rains and hail could transmit vibration into the roof and building structure. Once the vibrations are introduced into the structure, the sound produced can be audible great distances from the source. In addition to the impact noise caused by the rain and hail, the PV panels can vibrate due to wind forces; the vibrations of these panels can also induce low frequency sound within the building structure.

The connection detail between the PV system and building structure is critical in mitigating structure-borne sound. In discussions with the Structural Engineers, the concept for supporting the PV cells includes the use of 5" diameter standard pipe columns that would bear on the deck above the trusses and be thru bolted to the roof trusses. Refer to the Structural section of the Phase 2 report.

A system that would 'decouple' the PV panel supports from the building structure is recommend to mitigate the transmission of structure-borne sound. This can be achieved by introduction of a resilient material such as neoprene rubber mats between the pipe column supports; or isolating the attachment to the building trusses using springs. Decoupling options are further described below. Additional sketches and technical information for each are included at the end of this Appendix.

OPTION 1: Elastomeric Neoprene Rubber Pads. This option indicates the use of a thick rubber pad to isolate the pipe column supports for the PV panels. An oversized hole fitted with a neoprene rubber bushing must be provided to prevent a rigid contact with the thru-bolt and the building structure. These pads are most effective acoustically at high frequency isolation.

OPTION 2: Restrained Spring Isolators. In this option a spring would be used in lieu of a rubber pad to separate the pipe column supports from the building structure. The spring housing also contains bolts to resist wind uplift forces. Springs are used to support heavy equipment and are most effective acoustically at low frequency isolation.

OPTION 3: Neoprene-In-Shear Mounts. Similarly, these mounts should be incorporated at the base of the pipe column supporting the PV panels. In terms of effectiveness these isolators fall between rubber pads and springs as they isolate both high and low frequency.

The above three options are thought to be capable of providing the resiliency needed to decouple the PV panels from the building structure. In order for the selected option to perform effectively, it must be appropriately sized to avoid overloading the isolators.

In the case of the springs, the springs must be compressed to achieve the ideal isolation performance. The PV panels may be too light and additional weight may be needed in order to properly deflect the springs.

The costs for these “decoupling” connections can range as follows:

- Option 1: Kinetics Elastomeric Isolator Model RSP are approximately \$3 per 2”x2” pads.
- Option 2: Kinetics Restrained Spring Isolator Model FLSS 4 are approximately \$500 per isolator.
- Option 3: Kinetics Elastomeric Isolators Model RD are approximately \$13 per isolator.

NEXT STEPS

Kirkegaard has identified three options to isolate the PV panels from the building structure. Within the scope of this Feasibility Study, however, it cannot be determined which option is most appropriate for the project. If the project is advanced to the design phase, additional analyses of the existing conditions and a mock-up are recommended as follows:

1. In-situ Isolation Testing – conduct impact isolation testing to measure the performance of the existing roof structure. This testing involves the use of a specialized tapping machine to meet current ASTM standards.
2. Further assess the structure for potential flanking paths for noise and vibration to gain a better understanding of the existing conditions and aid in the selection of an isolation approach.
3. Construct a full size mock-up or prototype installation of one of the PV panels on top of the roof. This is intended to simulate some of the conditions that the PV panels will encounter and provide the designers with better feedback than any computer model can predict. The mock-up would also be useful in confirming (or disproving) the assessment of the aesthetic impact of the installation of the PV array and could also aid in evaluating the effects of wind on the panels.

CONCLUSION

This Feasibility Study presents general considerations and possible options for noise and vibration mitigation that would be a necessary component of the installation of a photovoltaic array on the roof over the Great Hall. Recognizing that effective isolation of noise and vibration is critical to the function of this space, it is strongly encouraged that final selection of a vibration isolation system be guided by additional site assessments, including full scale mock-up testing.

Attachments

Roof / Ceiling Isolation


Conceptual Panel Support System

Panel Frame Decoupling– Option 1: Rubber Pads

Panel Frame Decoupling– Option 2: Spring Isolators


Panel Frame Decoupling– Option 3: Neoprene-In-Shear Mounts

EXISTING ROOF/CEILING ISOLATION




Kraannet - Photovoltaic study
CONCEPTUAL PANEL SUPPORT SYSTEM.


PARTIAL
PLAN



SECTION 1
(LOOKING NORTH)




In stall longitudinal bracing (knee braces) between col. lines G14 and G15



Option 1

KINETICS™

Elastomeric Isolators Model RSP



Application and Description

Kinetics RSP neoprene pads are produced from a high quality neoprene elastomer. Pads are 50 durometer and are designed for a maximum of 60 psi (4.2 kg. / sq. cm) loading. Pads are designed for a maximum deflection of approximately 20% of its unloaded thickness, 0.15" (0.38 cm). Several layers of RSP pads can be stacked for additional deflection when steel separation shim stock is used. The elastomer is oil and water resistant, offers a long life expectancy consistent with neoprene compounds, and has been designed to operate within the safe stress limits of the material. RSP pads are available in 18" x 18" x 3/4" (457 mm x 457 mm x 19 mm) thick sheets and are pre-scored into 2" x 2" (51 mm x 51 mm) squares.

Kinetics Model RSP elastomer in-shear isolation pads are suitable for the isolation of noise, shock, and high frequency vibration produced by mechanical, industrial, or process equipment located on grade, structural slab, or in other non-critical areas.

Applications for Model RSP pads should be limited to pad loadings not to exceed 60 lb. / sq. inch (4.2 kg. / sq. cm.) and are typically used with equipment or machinery having lowest operating speeds of 3600 rpm. Under shock or impact loading, the load capacity of the pads should be reduced by 50%.

Features

- Elastomer in-shear neoprene pads
- Oil, Water, and Corrosion resistant
- Available in 18" x 18" x 3/4" (457 mm x 457 mm x 19 mm) sheets, scored into 2" x 2" (51 mm x 51 mm) squares
- Load Capacities from 10 (0.7 kg. / sq. cm.) to 60 (4.2 kg. / sq. cm.) psi
- Static Deflections up to 0.15" (4 mm)

Specifications



Isolation pads shall be neoprene elastomer in-shear pads, used in conjunction with steel shims where required, having static deflections as tabulated.

All pads shall be elastomer in-shear and shall be molded using 2500 psi minimum tensile strength, oil resistant neoprene compounds with no color additives.



Pads shall be 50 durometer and designed to permit 60 psi (4.2 kg. / sq. cm.) loading at a maximum rated deflection of 0.15" (4 mm). Pads shall be available in 18" x 18" x 3/4" (457 mm x 457 mm x 19 mm) thick sheets, scored into 2" x 2" x 3/4" (51 mm x 51 mm x 19 mm) thick pads. When two isolation pads are laminated, they shall be separated by, and bonded to, a galvanized steel shim plate.

Neoprene vibration isolators shall have minimum operating static deflections as shown on the Vibration Isolation Schedule, or as indicated on the project documents, but not exceeding published load capabilities.

Neoprene vibration isolators shall be model RSP as manufactured by Kinetics Noise Control, Inc.



Full Sheet is 18" x 18" x 3/4"
 Contains 81 - 2" x 2" Pads
 Max. Load Rating for each 2" x 2"
 Pad is 240 lbs. (109 Kg)



United States


6300 Irelan Place
 P.O. Box 655
 Dublin, Ohio 43017
 Phone: 614-889-0480
 Fax: 614-889-0540

Canada

3570 Nashua Drive
 Mississauga, Ontario
 L4V 1L2
 Phone: 905-670-4922
 Fax: 905-670-1698

www.kineticsnoise.com
sales@kineticsnoise.com

Kinetics Noise Control, Inc. is continually upgrading the quality of our products. We reserve the right to make changes to this and all products without notice.



Option 2

Restrained Spring Isolators Model FLSS 4

Description

Kinetics Model FLSS Seismic Control Restrained Spring Vibration Isolators consist of free-standing, large diameter, laterally stable steel springs assembled into welded steel housing assemblies. The housings are fabricated to limit vertical movement of the isolated equipment if equipment loads are reduced or if the equipment is subjected to large external forces such as high winds or seismic events. The housings also provide a constant free and operating height to facilitate installation.

Spring elements are complete with internal noise isolation pads and leveling bolts as a part of the top load plate assembly. Holes are provided in all isolators for bolting to the structure and the supported equipment. To assure stability, the springs have a lateral spring stiffness greater than 1.2 times the rated vertical stiffness and are designed to provide a minimum overload capacity of 50%.


FLSS isolators are available with deflections to 4 in. (100 mm) and with load capacities to 23,200 lbs. (10523 kg) as standard products. Custom isolators with higher deflection and greater load capabilities are also available. Kinetics Model FLSS Spring Isolators are recommended for the isolation of vibration produced by equipment carrying a large fluid load which may be drained, such as boilers and chillers, and for the isolation of cooling towers, air-cooled condensers, etc., where motion due to wind loads must be minimized.

Application

Kinetics Model FLSS Seismic Control Restraint Spring Isolators are recommended as a noise and vibration isolator for mechanical equipment under the following conditions:

1. When the mechanical equipment is located above or near noise and vibration sensitive areas.
2. When the mechanical equipment is subjected to seismic events, high wind loads or other external forces.
3. When the equipment to be isolated has significant changes of weight due to fluid drainage during maintenance operations such as boilers, chillers and cooling towers.

Operating static deflections are available up to 4 in. (100 mm) to maintain a high degree of noise and vibration control while compensating for long span flexible floor structures.



Specification

Vibration isolators shall be seismically rated, restrained spring isolators for equipment which is subject to load variations and large external forces. Isolators shall consist of large diameter, laterally stable, steel springs assembled into welded steel housing assemblies designed to limit movement of the supported equipment in all directions.

Housing assembly shall be of fabricated steel members and shall consist of a top load plate complete with adjusting and leveling bolts, adjustable vertical restraints, isolation washers, and a bottom plate with internal non-skid noise isolation pads and holes for anchoring of housing to supporting structure. Housing shall be hot-dip galvanized for corrosion resistance. Housing shall be designed to provide a constant free and operating height within 1/8 in. (3 mm).


The isolator housing shall provide seismic and wind restraint required by current building codes.

Spring elements shall be selected to provide static deflections as shown on the vibration isolation schedule or as indicated or required in the project documents. Springs shall be color coded or otherwise identified.

Spring elements shall have a lateral stiffness greater than 1.2 times the rated vertical stiffness and shall be designed to provide a minimum of 50% overload capacity. Non-welded spring elements shall be polyester powder coated, and shall have a 1000 hr rating when tested in accordance with ASTM B-117.

Vibration isolators shall be Model FLSS as manufactured by Kinetics Noise Control, Inc.

Isolator Type	Spring Color	Rated Capacity		Rated Deflection		Spring O.D.		L		W		D		d		H	
		lbs.	kg	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm
FLSS-4-100	Gray	100	45	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-250	Blue	250	113	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-500	Grn	500	227	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-750	Black	750	340	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-1000	Red	1000	454	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-1250	Brown	1250	567	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-1600	Orange	1600	726	4.00	102	5.63	143	11.00	279	6.00	152	0.69	17	0.56	14	14.00	330
FLSS-4-2250	Beige	2250	1021	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-2500	Bge/Blu	2500	1134	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-2750	Bge/Grn	2750	1247	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-3000	Bge/Blk	3000	1361	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-3250	Bge/Red	3250	1474	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-3500	Bge/Brn	3500	1588	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-3850	Bge/Org	3850	1746	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-4200	Chrome	4200	1905	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-4450	Chr/Blu	4450	2018	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-4700	Chr/Grn	4700	2132	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-4950	Chr/Blk	4950	2245	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-5200	Chr/Red	5200	2359	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-5450	Chr/Brn	5450	2472	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-5800	Chr/Org	5800	2631	4.00	102	8.00	203	16.25	413	8.00	203	0.69	17	0.69	17	17.25	381
FLSS-4-5500	Bge/Grn	5500	2495	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-6000	Bge/Blk	6000	2722	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-6500	Bge/Red	6500	2948	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-7000	Bge/Brn	7000	3175	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-7700	Bge/Org	7700	3493	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-8400	Chrome	8400	3810	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-8900	Chr/Blu	8900	4037	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-9400	Chr/Grn	9400	4264	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-9900	Chr/Blk	9900	4491	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-10400	Chr/Red	10400	4717	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-10900	Chr/Brn	10900	4944	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-11600	Chr/Org	11600	5262	4.00	102	8.00	203	26.00	660	8.00	203	0.69	17	0.69	17	17.25	387
FLSS-4-11000	Bge/Grn	11000	4990	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-12000	Bge/Blk	12000	5443	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-13000	Bge/Red	13000	5897	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-14000	Bge/Brn	14000	6350	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-15400	Bge/Org	15400	6985	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-16800	Chrome	16800	7620	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-17800	Chr/Blu	17800	8074	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-18800	Chr/Grn	18800	8528	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-19800	Chr/Blk	19800	8981	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-20800	Chr/Red	20800	9435	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-21800	Chr/Brn	21800	9888	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387
FLSS-4-23200	Chr/Org	23200	10523	4.00	102	8.00	203	27.00	686	17.00	432	0.81	21	0.69	17	17.25	387




United States
6300 Irelan Place
P.O. Box 655
Dublin, Ohio 43017
Phone: 614-889-0480
Fax: 614-889-0540

Canada
3570 Nashua Drive
Mississauga, Ontario
L4V 1L2
Phone: 905-670-4922
Fax: 905-670-1698

www.kineticsnoise.com
sales@kineticsnoise.com

Kinetics Noise Control, Inc. is continually upgrading the quality of our products. We reserve the right to make changes to this and all products without notice.



Option 3

KINETICS™


Elastomeric Isolators Model RD

Description

Kinetics Model RD Vibration Isolators are one-piece molded neoprene mounts with encapsulated metal inserts, are color coded to identify capacity, and have non-skid ribs on the bottom load surfaces. Each isolator incorporates two bolt-down holes on the bottom load surface and a tapped steel load top plate for attachment to the supported equipment. The neoprene is highly oil resistant and has been designed to operate within the strain limits of the isolator to provide maximum isolation and longest life expectancy possible using neoprene compounds. Model RD is designed for up to 0.5" (13 mm) deflection, available in four sizes and eleven capacities from 55 lbs. to 4,000 lbs. (25 kg to 1814 kg). Kinetics Model RD is recommended for the isolation of vibration produced by small pumps, vent sets, low pressure packaged air-handling units, etc., and is usually selected when first cost must be minimized.

Features

- Molded neoprene isolator
- Cast-in tapped steel load plate
- Cast-in drilled steel anchor/baseplate
- Load capacities 55 pounds to 4000 pounds (25 kg to 1814 kg)



Application

Kinetics Model RD neoprene isolation mounts can be used to isolate noise and high frequency vibration generated by mechanical equipment located on a grade-supported structural slab or pier.

Typical applications of Model RD neoprene isolators are limited to isolation of mechanical equipment having the lowest operating speeds of 1750 RPM when located on a grade-supported slab or pier, and include close-coupled pumps with motors of 5 H.P. or less, small vent sets, low pressure packaged air-handling units, and similar equipment types.

Model RD neoprene isolation mounts can be used for isolation of mechanical equipment specified to be supported by neoprene rubber or elastomer isolators and with tabulated minimum static deflection up to 0.50" (13 mm).


Isolator Type	Color	Duro	Rated Load		Rated Deflection		L		W		A		B		C		D		E		H	
			lbs	kg	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm
RDA-55	Yellow	50	55	25	0.40	10	3.19	81	1.81	46	1.25	32	0.31	8	2.38	60	0.34	9	0.19	5	1.50	38
RDA-125	Blue	70	125	57	0.40	10	3.19	81	1.81	46	1.25	32	0.31	8	2.38	60	0.34	9	0.19	5	1.50	38
RDB-120	Orange	45	120	54	0.50	13	3.88	98	2.38	60	1.75	44	0.38	10	3.00	76	0.34	9	0.25	6	1.75	44
RDB-220	Green	55	220	100	0.50	13	3.88	98	2.38	60	1.75	44	0.38	10	3.00	76	0.34	9	0.25	6	1.75	44
RDB-375	Blue	65	375	170	0.50	13	3.88	98	2.38	60	1.75	44	0.38	10	3.00	76	0.34	9	0.25	6	1.75	44
RDC-250	Yellow	55	250	113	0.50	13	5.50	140	3.25	83	2.50	64	0.50	13	4.13	105	0.56	14	0.25	6	2.50	64
RDC-600	Blue	60	600	272	0.50	13	5.50	140	3.25	83	2.50	64	0.50	13	4.13	105	0.56	14	0.25	6	2.50	64
RDC-1100	White	70	1100	499	0.50	13	5.50	140	3.25	83	2.50	64	0.50	13	4.13	105	0.56	14	0.25	6	2.50	64
RDD-2250	Red	50	2250	1021	0.50	13	6.25	159	4.63	118	3.75	95	0.50	13	5.00	127	0.56	14	0.38	10	2.75	70
RDD-3000	Green	60	3000	1361	0.50	13	6.25	159	4.63	118	3.75	95	0.50	13	5.00	127	0.56	14	0.38	10	2.75	70
RDD-4000	Gray	70	4000	1814	0.50	13	6.25	159	4.63	118	3.75	95	0.50	13	5.00	127	0.56	14	0.38	10	2.75	70

Specifications

Vibration isolators shall be neoprene, molded from oil-resistant compounds, with cast-in-top steel load transfer plate for bolting to supported equipment, and a bolt-down plate with holes provided for anchoring to supporting structure. Bottom surfaces shall have non-skid ribs.

Neoprene vibration isolators shall have minimum operating static deflections as shown on the Vibration Isolation Schedule or as indicated on the project documents but not exceeding published load capabilities.

Neoprene vibration isolators shall be Model RD, as manufactured by Kinetics Noise Control, Inc.



kineticsnoise.com/hvac/rd.html
 sales@kineticsnoise.com
 1-800-959-1229

Dublin, Ohio, USA

Las Vegas, Nevada, USA

Toronto, Ontario, Canada

Hong Kong, China

Appendix C

Opinion of Probable
Construction Cost - General Work



OPINION OF PROBABLE COST

PROJECT	Krannert PV Study	SUBMITTAL NO.	Study Phase 2
LOCATION	Urbana, IL	TRADE	Gen_Struct
ARCHITECT	Hanson Professional Services Inc.	ENGINEER	Hanson Professional Services Inc.
DATE	3/24/2014	PREPARED BY	Fiorito / Svoboda / Wilkinson
PRICES BY	2013 RS Means	CHECKED BY	G. Clack

Division Reference	Div. #	Description	QTY	UNIT	UNIT MAT'L	EXT. MAT'L	UNIT LABOR	EXT. LABOR	UNIT TOTAL INCL O&P	EXT. TOTAL INCL O&P	
Custom	07	ROOFING REPLACEMENT New Roofing	18000	SF					20.00	360000.00	
15419500600		CONSTRUCTION ACCESS AND GENERAL CONSTRUCTION									
	02	Crane Mobilization	2	LS					3000.00	6000.00	
	02	Crane Time for PV Installation (OT)	32	Hr					505.00	16160.00	
	02	Demobilization	2	LS					3000.00	6000.00	
015423702250	01	Access Scaffolding Rent							277.00		
	01	Scaffolding	20	Ea	32.00	640.00			35.20	704.00	
015423702900	01	Stair	10	Ea	40.00	400.00			44.00	440.00	
Custom	01	Setup	8	Hr			180.00	1440.00	277.00	2216.00	
15433403500	15	Light Plant	2	M					1724.80	3449.60	
Custom	03	Concrete Support Walls	30	CY					500.00	15000.00	
31113852100	03	Wall Forms	1050	SF					8.05	8452.50	
51223751300	05	Wide Flange Dunnage	926	LF	55.13	51050.38	4.68	4333.68	70.71	65477.46	
51223171100	05	Wide Flange Framing	926	LF	55.13	51050.38	4.68	4333.68	70.71	65477.46	
	05	Galvanizing	20372	LB	0.25	5093.00			0.28	5704.16	
	05	OT Erection	926	LF			2.34	2166.84	2.69	2490.94	
Custom	05	ROOF SCUTTLE IMPROVEMENTS New Hatch	1	LS					15000.00	15000.00	
Custom	05	ROOF TRUSS STRENGTHENING Truss Strengthening and Access	1	LS					300000.00	300000.00	
CUSTOM	13	NOISE AND VIBRATION MITIGATION Isolators	48	EA	500.00	24000.00	250.00	12000.00	750.00	36000.00	
MAT'L TOTAL					81183.38	LAB'R TOTAL		19940.52	TRADE TOTAL		843094.66